

Diagram No. 1117

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SERVICE

DESCRIPTIVE REPORT

Type of Survey Hydrographic

Field No. R/H-20-5-77
Registery No. FE-285WD

LOCALITY

State Texas

General Locality Gulf of Mexico

Sublocality Offshore Freeport

1977

CHIEF OF PARTY
LCDR R.V.Smart

LIBRARY & ARCHIVES

DATE January 14, 1987

☆U.S. GOV. PRINTING OFFICE: 1985-566-054

1

TO SIGN OFF SEE
"RECORD OF APPLICATION"

FORM C&GS-537

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

REGISTER NO.

HYDROGRAPHIC TITLE SHEET

FE-285WD

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.

FIELD NO. ***///-**| 20-5-77,20-6-77,20-8-7

State TEXAS	/
General locality GULF OF MEXICO	V
LocalitySEADOCK Offshore Freeport	/
Scale 1:20,000 \$ 1:40,000 (smooth plot) Date of survey 9 June 29 October 197	7
Instructions dated 22 April 1977 Project No. OPR- 479-RU/HE-1977	-
Vessel RUDE & HECK	-
Chief of party R. V. SMART, LCDR., NOAA	V
Surveyed by LCDR. R.V. SMART, LCDR. T. RUSZALA, LTJG. K.G. VADNAIS, LTJG. C.E. GROSS, ENS. S.P. De Bow, ENS. M.A. CLASSICK	
Soundings taken by eeho sounder, hand lead, pole wire drag	~
Graphic record scaled by NA	~
Graphic record checked by NA	5
Protracted by N/A Automated plot by Rough plot only	シレ
Soundings penciled by Evaluation and Analysis Group, AMC	~
Soundings in MAXXX feet at MLW XXXX predicted tides (smooth tides)	~
	\exists
REMARKS:	- 1
STANDANDS CK'D 1-20-87 C.Loy	
	_
	_
	-
	_
	_
Awois and SURFV 489 S03	

TABLE OF CONTENTS

I. A. AUTHORITY

- B. CHARACTERS AND LIMITS OF WORK
- C. CONTROL
- D. SHORE SIGNALS AND CALIBRATION
- E. RAYDIST LANE LOSS
- F. DATES OF SURVEY
- G. TIDE REDUCERS
- H. JUNCTIONS AND SPLITS
- I. INCOMPLETE ITEMS
- J. CURRENTS AND WINDS
- K. DIVING PROCEDURES
- L. TESTING
- M. GENERAL NOTES
- N. DESCREPANCIES WITH RECENT CHARTS
- O. PERSONNEL AND EQUIPMENT
- P. APPROVAL

II. ITEM 1

- A. STATEMENT ON ITEM 1
- B. GROUNDINGS AND HANGS
- C. NOTED OCCURANCES DURING SURVEY
- D. SUMMARY
- E. RECOMMENDATIONS

III. ITEM 5

- A. STATEMENT ON ITEM 5
- B. GROUNDINGS AND HANGS
- C. NOTED OCCURRENCES DURING SURVEY
- D. SUMMARY
- E. RECOMMENDATIONS

IV. ITEM 3

- A. STATEMENT ON ITEM 3
- B. GROUNDINGS AND HANGS
- C. NOTED OCCURRENCES DURING SURVEY
- D. SUMMARY
- E. RECOMMENDATIONS

V. ITEM 5a

- A. STATEMENT ON ITEM 5a
- B. GROUNDINGS AND HANGS
- C. NOTED OCCURRENCES DURING SURVEY
- D. SUMMARY
- E. RECOMMENDATIONS

VI. ITEM 2

A. STATEMENT ON ITEM 2

VII. LIST OF ATTACHMENTS

* I. DAILY RAYDIST CORRECTORS

LIST OF ATTACHMENTS

- II. STATISTICS
- III. LIST OF HANGS
 - IV. PARAMETERS
 - *A. ELECTRONIC CONTROL PARAMETERS
 - *B. PROJECTION PARAMETERS
 - C. G.P.S OF SIGNALS AND ITEMS
- * V. AREA OF SEARCH FOR SEADOCK
- *VI. PROJECT INSTRUCTIONS
- * VII. COPY OF DESCRIPTION OF VADNAIS DATA ACQUISITION SYSTEM
- * = Data removed from the Descriptive Report and filed with the field records.

DESCRIPTIVE REPORT

TO ACCOMPANY FE-285 WD

WIRE DRAG FIELD NDS. 20-5-77, 20-6-77, 20-8-77 SEADOCK, LOOP, SAFTEY FAIRWAYS

GULF OF MEXICO 1977

LT. CDR. R. V. SMART NOAA SHIPS RUDE & HECK

A. AUTHORITY

This project was authorized under Project Instructions OPR-479-RU/HE-77, Wire Drag, Gulf of Mexico Investigations, dated 22 April, 1977 and amended by Change No. 1 dated 29 September, 1977.

B. CHARACTER AND LIMITS OF WORK

The purpose of this work was to conduct wire drag operations on the pre-construction phase of Seadock and Loop Deepwater port facilities off of Freeport, Texas and Grand Isle, Louisiana, respectively.

The area covered during the project consisted of four items (*1,*3,*5,\pm,*5a) \circ\contained in the Seadock area on Chart 11300.

C. CONTROL - RAYDIST AND DEL NORTE STATIONS

Raydist DR-S Range-Range control was the primary control used during the survey. The stations operated on a frequency of 3294.4 KHZ which provided a lane width of 45.481635 meters. Two raydist shore stations were used, one at the southern end of Galveston Island (designated H-1-TX-77) and located at Lat. 29°14"33.0460"N and Long. 94°52'08.3688"W (RED). The other station (GREEN) was located at the U.S. Army Corp of Engineers, Brazos River Floodgates in Freeport, Texas, designated H-2-TX-77) at Lat. 28°53'A9.9729"N, and Long. 95°-22'56.3698"W.—These Stations could not be verified—See sections Za, and 4 of the Modified Explosion Report.

In addition to Raydist, three Del Norte trisponder stations were used in order to facilitate in calibration of the Raydist unit on board the RUDE. One unit was located at a fishing pier in Surfside, Texas at Lat. 28°57'27.9041" and Long. 95°16'24.3318. The second station was located at the U.S. Coast Guard base in Freeport, Texas at Lat. 28°56'27.73"N and Long. 95°18'03.7624". The final station was erected atop the grean Raydist station in Freeport, Texas at Lat. 28°53'49.9729"N and Long. 95°22'56. 3698"W.—These stations could not be verified—See sections 2.a. and 4. of the Modified Evaluation Report.

Radar ranges between the two vessels were recorded each fix. Along with the bearings to the ships, this puts a limit on any lane ambiguity, if one vessel's Raydist control remains good.

The radar ranges were interpolated between guarter mile rangerings, and their accuracy is considered accurate to within about 0.05 nautical miles.

D. SHORE SIGNALS AND CALIBRATION

Calibration of the Raydist was accomplished, primarily, through the use of sextant angles to shore signals of known co-ordinates.

In addition, a Del Norte net was used to facilitate calibration at night and also to check the Raydist unit during suspected lane loss. Calculation of the red and green lane values from this information was accomplished through the use of an HP-65 programable calculator. The shore signals and Del Norte trisponder sites were as follows;

ACE-Freeport Municipal Tank, 1954 Lat. 28°57'05."721N, X=3165 894.03 Long. 95°21'13."334W, Y=424 765.16

FUN-East Freeport Stafford Chemical Company Tank, 1931 Lat. 28°56'55."376N, X=3171 394.35 Long. 95°20'11."7 5W, Y=423 891.82

AIM-Dow Chemical Company Shop Water Tank, 1954 Lat. 28°56'45"826N, x1=3176 185.67 Long. 95°19'18."135W, Y=423 077.30

WAD-Dow Chemical Company Organic Water Tank, 1954
Lat. 28°56'47."542N/ X 3178 512.12/
Long. 95°18'51."873W, Y= 423 323.96/

ION-Freeport East Jetty Light (Freeport Entrance Light 6)
Lat. 28°55'40."7608N, X=3187044.56
Long. 95°17'18."1897W, Y=416 846.07

Unverified *

COD-Freeport West Jetty Light (Freeport Entrance Light 7)
Lat. 28°55'41."432N, X=3186 198.07
Long. 95°17'27."6971W, Y= 416 887.03 Univerified **

EVA-Fishing Pier (end)
Lat. 78°57'26."1275N, X=3191636.79
Long. 95°16'22."6625W, Y=427638.87

Universitied **

DEL NORTE REMOTE UNITS

Code 74 Station - Atop Green Raydist Tower
Lat. 28°53'49"973N, X= 3157356.88
Long. 95°22'56."3698W, Y= 404721.19

Unverified **

Code 72 Station - Atop C.G. Base Freeport Building Lat. 28°56'27."73N, X=3182847.29
Long. 95°18'03."7624W, Y= 421459.00

* = Station which could not be verified as no data could be found. See sections 2.a. and 4. of the Modified Evaluation Report. Code 78 Station - Located Atop Fishing Pier
Lat. 28°57'27."9041, X= 3191482.867
Long. 95°16'24."3318, Y=427813.473

NOTE: X and Y in Feet.

Of the Modified Evaluation Report.

E. RAYDIST LANE LOSS

Throughout the project, lane loss due to thunderstorms and other atmospheric conditions was a limiting factor affecting quality data accumulation. Since the working grounds were approximately 48 miles from the Raydist stations at times, any small amount of thunderstorm activity would cause the ships to lose lock on the signals. For this reason, a minimum of 30 days of production were lost.

An apparent inshore effect caused the ships to lose lock on the Raydist signal on H, M, and N days. This problem was frequently encountered when the ships would anchor at night off of the calibration area in order to calibrate at daylight. In the interim, both ships lost lock on the signal and after calibration the discrepancy was computed.

F. DATES OF SURVEY

The actual survey began in the Seadock work area on 9 June 1977 and was ended on 29 October 1977.

G. TIDE REDUCERS - Smooth Tides have been applied to all the verified survey data.

Field reduction of each day's data was done using predicted tides for Galveston, Texas with the following correctors applied:

Time	Height	Ratio

Items 1, 2, & 3 H.W.=1 hr., 37 min L.W.=1 hr., 38 min. 0.93 Items 4,5, & 5a H.W.=1 hr., 54 min L.W.=1 hr., 55 min. 0.93

H. JUNCTIONS AND SPLITS - None

I. INCOMPLETE ITEMS

According to the project instructions, a total of 18 items were to be surveyed this season, 6 of which were in the Seadock area. Due to uncontrollable circumstances (weather, electronics failure, etc.) only Items 1, 3, 5 and 5a were completed this season. One drag was run on Item 2 but it had to be rejected.

J. CURRENTS AND WINDS

Currents in the area were minimal most of the season and had very little effect on the drag. At the start of the season,

it was thought that excessive lifts were due to subsurface layered currents. However, it was later discovered that the vertical component of the short towline (1000 feet) in relation to depth and length of the drag was the reason for the lifts. This problem was rectified by lengthening the towline to 1400 feet, removing toggles from the towline, and adding an extra shackle to each toggle on the ground wire.

Even though it was thought that currents in this area of the Gulf of Mexico were negligible, a current test was run each time the ships arrived at the working grounds. After a number of these tests, it was found that the maximum velocity in the area was not greater than 0.2 knots.

Being 40-50 miles offshore for most of the project, the ships were virtually at the mercy of the weather. Localized thunderstorms would appear without warning causing the ships to lose lock on the Raydist signal. On the other hand, winds consistently blowing in excess of 15 knots were encountered on many days of the project. With a wind of this intensity from the south or southeast, the seas would build in excess of 3 feet due to unlimited fetch. Consequently, effective wire drag could not be accomplished due to excessive lifts and the ships would have to wait for the seas and winds to subside.

K. DIVING PROCEDURES

Diving procedures on this project pertained only to Item 5a since it was the only item of the project where a hang was encountered. Partial wet suits were worn due to the warm water. Visibility ranged from 10 to 30 feet and least depths were determined using both digital and oil filled depth gages. Least depths from diver wrist depth gages are not acceptable in meeting survey standards.

L. TESTING

Testing results were recorded in both the rough and smooth tester volumes. The rough tester records the actual height of the mark on the tester pole after pick-up. In the smooth tester record, the test was recorded corrected to the wire depth. The smooth test record shows the actual lift and sag.

In the smooth test record an asterick (*) next to the section indicates the test came from the HECK's Launch - 20.

Definition of a sag miss: A test in which the tester rod has definitely been thrown in ahead of the ground wire, and picked up after the ground wire has passed yet has no marks on the pole. The wire is assumed to have passed underneath the tester rod and the test is considered valid providing a maximum value for the amount of lift present.

Definition of a TOB: TOB refers to "tester on bottom". It is a test result that occurs when the tester rod shows signs of having touched the ocean floor. Lifts associated with this type of test generally are not accepted because of the uncertainity as to where the ground wire struck the rod. It is likely that if the tester rod is stuck in the ocean floor the ground wire might first ride up the rod until enough force is generated to push the rod away.

M. GENERAL NOTES

It is important to know that the ships are moving properly at the close of the drag. Before Raydist it was difficult to see if the ships were moving without taking a complete fix. The Raydist's saw tooth recorder gives a permanent record of movement of the ships at all times. The Raydist strip chart was checked at the end of each drag to ascertain proper ship movement before the drag was aborted.

By the use of the saw tooth strip chart, one can tell the path of the ships between fixes. This fact may be important in specific cases where it is possible that between fixes the proper overlapping may not have been met.

Relative Pen Lengths: In most cases, the three strip chart pens were not exactly the same length, making proper interpretation of the record impossible without the appropriate adjustments. Relative pen lengths, entered on the strip charts by means of completing a rubber stamp, were noted each day.

All buoy and tester uprights were personally verified correct by the Officer-in-Charge before the project began. Those buoy and tester uprights which were used were verified correct to 125 feet (maximum use was 121 feet on "V" day).

N. DISCREPANCIES AND COMPARISON WITH RECENT CHARTS

Any discrepancies and comparison with recent charts are noted in the recommendations section of the item description at a later time in this report. See also section 7. of the Modified Evaluation Report.

O. PERSONNEL AND EQUIPMENT

During this survey the RUDE & HECK acted as quide and end vessel respectively. Both vessels are equipped with Raytheon DE-723 fathometers for recon hydro. Both of the vessels Bristol launches were utilized as drag tenders. Bearings to the end buoys and opposite vessel were made on Sperry Gyro Repeaters. Standard wire drag equipment was used throughout this survey. The officers participating were:

LCDR R. V. Smart, LCDR T. Ruszala, LTJG K. G. Vadnais, LTJG C. E. Gross, ENS S. P. De Bow, and ENS M. A. Classick.

Lt. Cdr. R.V. Smart, Lt. Cdr. T. Ruszala, Lt. (JC) K. G. Vadnais, Lt. (JG) C. Gross, Ens. S. P. DeBow and Ens. M. A. Classick.

P. APPROVAL

All records of this survey, including smooth plotting, except for the addition of the effective depths (which must await smooth tides) and the drafting of a composite A & D sheet, are hereby approved. The field work was personally supervised by the undersigned. The boat sheets and records were inspected daily. The survey is considered complete and adequate for charting.

Submitted by:

S.P. DeBow, Jr. Operations Officer

NOAA Ships RUDE & HECK

Samuel P. St Bow, Jr.

Approved by:

R. V. Smart

Commanding Officer

NOAA Ships RUDE & HECK

Robert V. Smart, LT. COR., NO AA

II. ITEM 1

A. Statement on Item 1

Item 1 consisted of a 22-foot wreck charted at Lat. 28°36', Long. 95°03' in 96 feet of water.

B. Groundings and Hangs

There were no hangs encountered during the dates of coverage, A-F days inclusive.

C. Noted Occurances During Survey

At the start of the survey excessive lifts were encountered during the drags. These lifts were thought to be caused by subsurface currents in the area. Since there was no evidence to this effect, the command decided to vary the length between sections and vary the length of the towline until an acceptable level of lifts were encountered.

On "D" day, a power failure at the green station caused both of the vessels to gain one lane on the green rate. Since the lane gain was noticed between Positions 14 and 15, an additional lane was added to the green rate plots for the rest of the drag. In addition, extra overlap was allowed on the drags of "F" day in order to guarantee complete coverage of the area in question. This explanation is confusing by stating that one lane was gained and was thus corrected by adding one lane. In the field records the appropriate lane.

D. Summary corrections were made to the data by the field personnel.

Item I was covered to a one mile radius circle about the given position of the wreck. There was no evidence of a hang throughout the drags investigation

E. Recommendations

Although clearing an area by wire drag does not disprove the existance of a possible wreck, consideration should be given to changing the wreck to a Position Doubtful (PD) rather than the Position Approximate (PA) which exists on the chart (11300) at this time. The item is properly charted as a non-dangerous wreck since an effective depth, based on predicted smooth tides, of 90-132 feet was the shoalest reported over the item.

III. ITEM 5 See section 7. a. 1) of the Modified Evaluation Report.

A. Statement on Item 5

Item 5 was the wreck of the 55-foot trawler "SINTPAT" reportedly burned and sunk in 80 feet of water at Lat. 28°24'N, Long. 94°54'W. Since the reported depth of 80 feet is inconsistent with the hydrography in the area, the position or depth may be in error.— Concur.

B. Grounding and Hangs

There were no groundings or hangs encountered during the dates of coverage, i.e. "G" through "L" days inclusive.

C. Noted Occurances During the Survey

The first drag on the item, G-1, was rejected due to extreme lifts. On the second drag of the day, the lifts were again some what excessive. In an effort to reduce these lifts, the towline was lengthened to 1400 feet and the speed of the drag was decreased. As a result, lifts decreased substantially and this method was utilized for the rest of the project.

The drag on "H" day was rejected due to Raydist lane loss before closing calibration. This loss was discovered on the red signal by passing a marker buoy close abeam at the termination of the drag.

On "J" day lane continuity was checked on the marker buoy at the end of the drags. However, while steaming the 30 miles inshore in order to calibrate, thunderstorms destroyed the lock held by both vessels. Since the marker buoy established good lane count at the worksite, the data was kept and sufficient overlap was provided on adjoining strips.

The data accumulation on "L" day was hindered by the fact that the HECK's gyro repeaters had failed. A procedure was adopted by obtaining the relative bearings and noting the master gyroheading of the ship, both of which were recorded on the HECK and reduced to true bearing for the automatic data system. Reciprocal bearings checked by the RUDE agreed with those calculated from the HECK.

D. Summary

Item 5 was covered to a one mile radius circle about the given position of the wreck. There was no evidence of a hang throughout the drag. investigation

E. Recommendations

At the present time, the item is denoted on the chart as a sunken wreck dangerous to surface navigation with a "Position Approximate" symbol attached. Again, clearing an item by wire drag does not disprove the existance of a wreck. However, the least effective depth found over the area in question was 1152 feet, corrected to predicted tides. This fact could warrant the removal of the "Dangerous to surface Navigation" symbol. Also, the area was swept in a one-mile radius so that a "Position Doubtful" (PD) symbol could be considered adequate for this item. Concur-See section 7.a. 3) of the Modified Evaluation Report.

IV. ITEM 3

A. Statement on Item 3

Item 3 was reported to be a dangerous wreck, the F/V "Sadie S", located at Lat. 28°30'N, Long. 94°54'W.

B. Groundings and Hangs

One grounding was encountered on one of the rejected strips of "Q" day (Y.D. 255). However, this was expected as tides had fallen due to the slow progress of the drag and the buoy uprights were set very close to the ocean floor. Since the drag was eventually rejected, the grounding was not looked into at length because of the expectation of the event.

This grounding was exemined during processing and is not in conflict with either prior or subsequent.

C. Noted Occurances During Survey

The initial four drags on the item, two strips on both "M" and "N" days, were rejected due to the fact that lane loss was discovered at the close of the second drag of "N" day. Since we were in the working grounds on both days and a closing calibration was not completed before the loss, the data was rejected.

The first drag on "P" and "Q" days were rejected due to reoccuring problems with the Raydist units and thunderstorm activity. A total of six drags were rejected until one was acceptable without lane loss.

Drag P-1 was the first acceptable drag, yet a fouled upright was discovered during the drag. This caused a voided area from Position 1 to Position 25. After that position, lifts were found to be acceptable and the data was kept. The second drag of "P" day was run with the intention of providing coverage of the voided area.

On "R" day, the guide vessel had apparently lost 8 lanes on their red signal. As a result, single vessel control was used to obtain the guide vessel position. The single vessel control distances were calculated on the HP-65 programmagle calculator. Extra overlap was provided on additional strips to ensure coverage of the item.

"S" day was a day utilized as the initial investigation of the F/V First Mate which sank in the Seadock work area. This vessel later became Item 5a.

The initial drags on "U" day were rejected due to lane loss. However, the drag completed on the following day completed Item 3.

Not part of Item #3 investigation -

D. Summary

Item 3 was covered to a one mile radius about the given position of the wreck. There was no evidence of a hang throughout the survey on this item.

Recommendations

As was the case for Item 5, this item has a "Sunken wreck dangerous to surface Navigation" symbol on the present chart. Since it was found that the least effective depth over the item was 10% feet, it seems reasonable that this wreck can also be charted as a non-dangerous wreck.— Concur — See Section 7. a. 2) of the modified Evaluation Report.

V. ITEM 5a

Statement on Item 5a

Item 5a was the F/V "First Mate" sunk in Lat. 28°21.77'N, Long. 94°48.45'W reported by the RUDE & HECK as sinking on September 22, 1977, in approximately 130 feet of water. This item was added to the original project instructions by the amended Change No. 1, dated 29 September 1977.

Groundings and Hangs -by diver's wrist depth gage which is not acceptable for charting.

The two drags of "V"7 day, V-1 and V-2, hung the item at an effective depth of 104 feet and 97 feet, respectively. The least depth found on the wreck from diver investigation was approximately 93 feet. The vessel was hung at position Lat. 28°21.7%, Long. 94°48.'45W in 134 feet of water.

Two clearing strips were run on "W" day with a clearing depth of 93 feet and 92-1/2 feet respectively. However, the second drag of the day created ambiguity due to the fact that a temporary hang could have been encountered. This will be explained at length in the next section.

The item was also intentionally hung on drag X-1 at a depth of $\frac{94-1/2}{95}$ feet.

Noted Occurances During The Survey

On the initial hang of the item, V-1, divers attained a least depth by the use of a digital depth gage and conventional oil filled depth gages. - not acceptable for chanting.

The second drag, V-2, was run in an easterly direction, the opposite direction to the first drag, and was intended to hang the item in the opposite direction. Since no lifts were encountered well before the hang was indicated, an effective depth of 97 feet was found at the hang.

Drag W-1, was a clearing strip in one direction over this item. An effective depth of 93 feet was attained over the position of the initial hang of the item.

Drag W-2 was a reversal of drag W-1. The drag was believed to be acceptable in the field, however, upon receipt of the smooth plot, a temporary hang could have been encountered between Postions 20 to 25. This discrepancy was believed to be caused by the ships change in speed during the drag. Although this fact was not disproven in the field, the command feels as though it was not a temporary hang. However, since ambiguity does arise, the second clearing strip should not be accepted. On the other hand, diver investigation proved that the mast could be hung from any direction. Therefore, since the object was not smooth sloping, it is felt that one clearing strip is adequate for this item. The vessels' speed was reduced at position 20 and increased at position 25. There is no indication of unusual behavior in the busys that would indicate a possible hang. The wreck position was not passed until position 27 of this dray. The clearence depth of strip W-Z is considered valid.

The final drag on this item, X-1, was run with the intention of hanging the top of the mast, 3 feet below the depth at which it was cleared on "W" day. Diver investigation of the hang revealed that the wire had hung the mast approximately 1-1/2 feet below the top. The effective depth at this time was 94,1/2 feet, thus making 93 feet the shoalest point on the mast. - Concur; however, the 92-foot decrence by strip W-Z is the clearence depth recommended for charting.

D. <u>Summary</u>

The three hanging drags located the wreck at the same position each time. It is felt that the least depth of 9%2 feet is adequate for charting since the wreck was intact with an approximate 15° port list.

E. Recommendations

It is believed that the position of the wreck is exact for charting purposes. All three hangs placed the wreck at the exact same position each time. This command feels as though the clearing depth of 9% feet is adequate. Since the mast was erect, and not a smooth sloping object, it is felt that the clearing strip in one direction is sufficient for charting purposes. The minimum clearance of 92 feet is recommended for charting. See Section 7.a. 4) of the Modified Evaluation Report.

IV. ITEM 2

A. Statement on Item 2

One drag was run at the end of the season on Item 2. The drag was Y-1 but had to be rejected due to the fact that a lane discrepancy existed on the HECK and an upright was set at the wrong depth. Since this was the only drag done on the item and a large voided area existed because of the fouled upright, the drag was rejected. Investigation on a future date seems to be more reasonable.

Item 2. is considered as an uninvestigated item. All uninvestigated items of this project are recommended to be retained as presently charted and should be reassigned at an opportune time.

(4-30-57) (4-30-57) (6MM-DC 28424	LETTER			SNC			ж.	CORR.	OF DRAG	PLOT		ATTACH	MENT IIa	l	1
DAME.	DAY LE	STRIP	WOL. #	POSITIONS	L.N.M.	.N.M.	RED CORR.	GREEN C	LENGTH OF	SMOOTH					
DATE		S	>	A.	1	S	22	15		Š	REMA	RKS	γ	·	-
0 711170		 -		-] .
8 JUNE	_A	1	1	32	2.9	2.0			6000		Commer	ce work	on Item	1	}
9 June	В	1_1_	1	29	1.7	1.4			6000		Excessi	ve lift:	encoun	tered.	1
18 JULY	C	1	1	15	1 7	1.2		, -	6000		apparer	t layer	d curre	nts	1
]
19 JULY	D	1	1	30	2.7	2.3			6000		Lane ga 14-15	ined be	ween po	sitions	ļ
21 JULY	E	1	1	17	1.6	1.2			6000						
22 JULY	P	1	1	32	2.6	2.0			7200						1
	F	_2_	2	25_	2.3	1.4			4200		REDRAG	OF A-day			
27 JULY	G	1	2	18							Francei	vo 1164a	na4		
	G	2	2	36	2,6	2,1			5000		Initial	ve lifts drag of	item 5	ea	
28 JULY	Н	ì	2								I and lo	ss- not			
4 AUGUS		_									Dane 10	ss= not	usea		
4 AUGUS	J	2	2	33		2.1			6000 6000						
0 4370				·	5-01	1.0			3000						
9 AUG	K	2	<u>3</u> 3	36 22	2.7	1.4			4800						
					2.2	4.4			3600						
11 Aug	L L	1 2	3	16 17	1.0 1.2	0.6			1800		Coverag	e of hol	iday on	G day	
				± 1	102	0.7			1800		11	11	<u> </u>		
17 AUG	M M	1 2	4			,					Lane 1	oss - no	t used		1
			<u> </u>												,
18 AUG	N	1	4								Lane 1	oss - no	t_used		
20 SEPT	P	7	5	35	2.8	1 7			800						
	P	2	5	13	1.2	0.7			800		FIRST	trip of	Item 3		
21 SEPT	Q	1	6	32	2.7	1.6			4800						
22 SEPT	R	1	6		2.8				4800		C4 2				
				<u> </u>	0	- • -			7000		Single	vessel	control		
23 SEPT	S	1	6	0	0	0			N/R		Origina FIRST	l invest	igation	on F/W	
											PIROT	DATE			٠.
															•
	الرواي الموجه سال المراجع	Apple of the control		ار در در این در در د		San Printer			Since .	. Jillian	Section.	77		A CONTRACTOR OF THE SECOND	

10:K NO. 37 4-30-57) 08M-0C 28424	DAY LETTER	STRIP	VOL. #	POSITIONS	L.N.M.	S.N.M.	RED CORR.	GREEN CORR.	LENGTH OF DRAG	SMOOTH PLOT			MENT III	
DAIL		0,	-	Α.		S	<u>~</u>	3	1 1	S	REMA	RKS	1	T
F OOM		-	-	25	0.6	-			1.000		_			
5 OCT	T	1_	6	25	2.0	1,6			4800		Lane Del No	oss - Ri	DE clos CK Circ	es with
5 Oct	T	2	6	20	2.3	1.4			4800					
14 OCT	U	1	6	15	1.5	0.8			4800		Coverso	e of hol	day_ F	inish it
18 OCT	v	2	7	19 24	0.9	0.5			3200 3200		Begin w	ork on F g Item 5	V "MAT	"- Hang
												B 200m /		
19 OCT	W	1 2	7	15 16	0.9	0.6			3200 3200		Cleari	ng Strip	on Iter	7 5a
			·										 	
20 OCT	X	1	7	16_	0.9	0.4			3200		Final	Hang Of	5a- Dive	r Inves
28 OCT	Y	1	7	28							Lane 1	oss - No	t used	
$\overline{\wedge}$				ļ										
					-									
														1
	-			-										
				-										
i														
		•					-							
								ļ			•			
														<u> </u>
()——							,	 						
							· · · · · · · · · · · · · · · · · · ·							
					-									
				1				 						
	 													

OCK NO. 37 -30-57) -N-DC 28424 SITION NO.	-			GROUNDED EFF. DEPTH	D BY DAY	D EFF.	NG	СНАКТЕD DEPTH	A	TTACHMEN	T III	b
Y LETTER	BUOY NO.	LAT.	LONG.	GROUND	CLEARED BY STRIP NO.	CLEARED DEPTH	SOUNDING	CHARTE	REMARKS			
V-1	4-5	28°21.78		5	₩ <u>-1</u>	93			Origina MATE"	l hang d	f "FIRS	
V - 2	4-5	28°21'46.4" 28°21.78		5-	W-1	93			Hang in			
X-1	2-3	28021.78	94018 *11	5	w-2 N/A	92			Final h	ang of '	FIRST 1	MATE
]
									•			
] -
												¬ ¬.
												1
												ايمور ا اربع سراز إ
~												
												1
												- -, .
												_ : .
					ļ							
												ا: ا ا
	•											
										·		- Þ
					-							
											 	-:

G.P. s of Items (SEADOCK)

- 1. 28°36' N, 95°03' W
- 2. 28°33.5' N, 95°21.0' W
- 3. 28°30' N. 94°54' W
- 4. 28°24' N, 95°18' W
- 5. 28°24' N. 94°54' W
- 5a. 28°21.77' N, 94°48.45' W

G.P's of Signals

- 1. 28°57'05.721" NV 95°21'13.334" WV
- 2. 28°56'55.376" NV 95°20'11.755" WV
- 3. 28°56'45.826" N/ 95°19'18.135" W/
- 4. 28°56'47.542" NV 95°18'51.873" WV
- (5. 28°55'40.761" N 95°17'18.190" W
- 6. 28°55'41.432" N 95°17'27.697" W
- 7. 28°57'26.128" N 95°16'22.663" W

FREEPORT MUNICIPAL TANK, 1954

EAST FREEPORT STAFFORD CHEMICAL COMPANY TANK, 1931

DOW CHEMICAL COMPANY, SHOP WATER TANK,

DOW CHEMICAL COMPANY ORGANIC WATER TANK, 1954

FREEPORT EAST JETTY LIGHT (Freeport Entrance Light 6)

FREEPORT WEST JETTY LIGHT (Freeport Entrance Light 7)

FISHING PIER (end)

- Unverified

U.S. DEPARIMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

November 20, 1979

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic

Marine Center:

Hourly heights are approved for

Tide Station Used (NOAA Form 77-12):

877-1510 Galveston Pleasure Pier, TX

Period: June 8 - October 28, 1977

FE-285WD

HYDROGRAPHIC SHEET:

R/H 20-5-77, 20-6-77, 20-8-77

OPR:

479

Locality: Gulf of Mexico, off Texas coast

(Gulf Coast Low Water Datum): 2.86 ft.

Height of Mean High Water above Plane of Reference is 2.1 ft. - Calveston Pleasure Pier

REMARKS: Recommended zoning:

Apply +30 minute time correction and range ratio x0.86.

Chief, Datums and Information Branch

NOAA FORM 76-155 (11-72) NA	TIONAL	OCEANIC			C ADMINIS		30,	WE! NO	MDEN	
GEO		IIC NAM						FE-285	WD	
Name on Survey	·/A '	ON CHART ME	2 11330 p. 1013 p.	RVEY OURDR	ANGLE ANGLE ON ORMATI	or and	PS GRA	A WENTELL	S. Light L.	,; /
FREEPORT (title)	V									1
GULF OF MEXICO (title)	1									2
TEXAS (title)	j.									3
										4
										5
										6
										7
										8
										9
										10
										11
										12
								1		13
										14
										15
										16
					Approv	ed:				17
					0					18
					Che	rles	E. Ho	مئترد	atom	19
					Chief (eograp	her -N	1CG 2x	5	20
·					SEP	2319	86			21
·										22
			4	-, k/.=						23
										24
										25

HYDROGRAPHIC SURVEY STATISTICS REGISTRY NO.: FE-285WD

Number of positions		1286
Number of soundings		N/A
Number of control stations		11
	TIME-HOURS	DATE COMPLETED
Preprocessing Examination		
Verification of Field Data	147	13 SEPT 1986
Quality Control Checks		
Evaluation and Analysis	61	4 NOV 1986
Final Inspection	3	31 OCT 1986
TOTAL TIME	211	
Marine Center Approval		4 NOV 1986

Transmittal letter of survey and survey records will be included in the Descriptive Report to identify the records accompanying the survey.

ATLANTIC MARINE CENTER MODIFIED EVALUATION REPORT

SURVEY NO.: FE-285WD FIELD NO.: R/H-20-5-77

Texas, Gulf of Mexico, Offshore Freeport

SURVEYED: June 9 through October 29, 1977

SCALE: 1:20,000 and PROJECT NO.: OPR-479-RU/HE-77

1:40,000 (smooth plot)

SOUNDINGS: Wire Drag CONTROL: Raydist

(Range-Range)

1. INTRODUCTION

- a. The purpose of this survey is adequately defined in the Descriptive Report and the Project Instructions. Only Presurvey Review Items #1 (AWOIS #00255), #3 (AWOIS #00245), #5 (AWOIS #00236), and #5a (AWOIS #00227) were investigated by this survey. Processing of this survey has been modified so that only the verified hang, clearance and accompanying note on the wreck located, and the least clearance depths over the areas cleared by wire drag have been smooth plotted. This modified and limited processing is considered complete in regard to nautical charting requirements.
- b. A plot of the one verified hang, clearance and accompanying note and three plots of areas cleared by wire drag were generated and are attached to this report. These plots are considered the final plots or smooth sheets for this survey.
- c. Corrections and notes made by the evaluator to the Descriptive Report are denoted in red ink.

2. CONTROL AND SHORELINE

a. Four horizontal control stations used during this survey for calibrations are of Third Order, Class I accuracy or better, and are established on the North American Datum of 1927. One of these four stations contained a small error in the listed geographic position. Seven horizontal control stations (including the two Raydist station sites) could not

be verified. Positioning methods are adequately discussed in the Descriptive Report. Calibration methods are adequately discussed in the Descriptive Report but the field calibrations can only be partially verified as the field calibration records are incomplete. Control and calibration procedures are further addressed in section 4. of this report.

b. No shoreline exists within the limits of this survey.

3. HYDROGRAPHY

No sounding data was gathered during this survey.

4. CONDITION OF SURVEY

The adequacy of the final field sheets, survey records, and reports, and conformity to the requirements of the HYDROGRAPHIC MANUAL and the WIRE DRAG MANUAL were not considered during the modified processing of this survey except position control and calibration procedures and documentation. Position control was plagued with lane losses/gains throughout this survey. In most cases the electronic positioning problems or the extent of the problems were not evident until closing calibrations. strip chart records are not sufficient to resolve the control problems. Some calibrations of the Raydist systems were done by comparison with Del Norte range-range positioning which was not calibrated at any time during this The Raydist stations and the Del Norte stations used could not be verified as no records of their establishment could be found. Calibrations are incomplete in documentation and annotation. Calibration data for many of the survey days could not be found. Therefore, verification of position correctors and verification of lane losses/gains was not accomplished during processing. Only obvious positional errors were corrected during These control and calibration problems verification. adversely affect the quality and reliability of this survey; however, the wreck located by this survey was found in the same position on three separate days and the clearances gained over this wreck and over the other assigned items investigated were by sufficient overlap to justify the charting conclusions made in section 7. of this report.

5. JUNCTIONS

There are no junctions on this survey.

6. COMPARISON WITH SURVEYS

a. PRIOR SURVEYS

H-6291 (1937) 1:80,000 H-6398a (1938) 1:40,000

These prior surveys are common to the entire present No conflicts exist between prior hydrography and present effective depths. Prior hydrography ranges from 2 to 15 feet deeper than present survey effective depths within the common areas (except the area of Item #5a where the present survey clearance over the wreck is 42 feet shoaler than prior hydrography). Presurvey Review Item #5a (AWOIS #00227), the sunken wreck of the fishing vessel FIRST MATE, was not in existence at the time of the prior surveys; therefore, no conflict exists between prior hydrography and present hang and clearance depths on this wreck. Subsequent survey H-9885 (1980) is common to the entire investigations of Presurvey Review Items #1 (AWOIS #00255) and #3 (AWOIS #00245) and supersedes all prior hydrography within the common areas of these investigations.

It is not the intent of the present survey to supersede but only to supplement prior hydrography.

b. SUBSEQUENT SURVEY H-9885 (1980) 1:40,000

Subsequent survey H-9885 (1980) is common to the entire areas of investigation of Presurvey Review Items #1 (AWOIS #00255) and #3 (AWOIS #00245). Presurvey Review Items #5 (AWOIS #00236) and #5a (AWOIS #00227) are not common to any subsequent hydrographic surveys.

Within the common area of Presurvey Review Item #1 (AWOIS #00255) subsequent hydrography ranges from 7 to 11 feet deeper than the present survey clearance depth of 89 feet. No conflicts exist between present effective depths and subsequent hydrography except a submerged obstruction and a floating aid to navigation. The conflicting submerged obstruction and floating aid to navigation on survey H-9885 (1980) are common to an area cleared by 89 feet on the present survey. The obstruction is a submerged well in Latitude 28°35'57.02"N, Longitude 95°04'06.16"W with a shoalest sounding of 86 feet. This submerged well is identified in the U. S. Coast Guard (Eighth District) Offshore, Oil, Gas, Mineral and Related Structures including Sub-Sea Installations Listing as Tenneco 166 2 (TOC-GA-391-A&B). The floating aid to navigation, labeled as "HO 391#1", is the watch or station buoy for this submerged well and is privately maintained. It is unknown when the submerged well and buoy were established in this area but the present survey sufficiently proves that they did not exist at the time of present wire drag survey

operations. See section 7. of this report for charting recommendations.

Within the common area of Presurvey Review Item #3 (AWOIS #00245) subsequent hydrography ranges from 4 to 11 feet deeper than the present survey clearance depth of 108 feet. No conflicts exist between subsequent hydrography and present effective depths.

7.	COMPARISON	WITH	CHARTS	11300	(19th	Ed.,	Oct.	23,	<u> 1976)</u>
				11300	(26th	Ed.,	Aug.	17,	1985)
				11321	(17th	Ed.,	Jan.	17,	1976)
				11321					
									1985)

a. HYDROGRAPHY

The charted hydrography originates with the previously discussed prior and subsequent surveys. The previously discussed prior and subsequent surveys require no further consideration. Attention is directed to the following:

1) Presurvey Review Item #1 (AWOIS #00255), a charted nondangerous sunken wreck, position approximate in Latitude 28°36'N, Longitude 95°03'W, originated with Local Notice to Mariners No. 68 of 1965 and is identified as a 22-foot vessel which burned and sank in June of 1965. This wreck is presently charted (the 1984 and 1985 editions of the charts) as a nondangerous sunken wreck, position doubtful, in its previously reported position from advance information from the present survey (FE-285WD). This wreck was not found by the present survey. The present survey cleared a search area exceeding the required one nautical mile radius circle of search around the reported position by a minimum effective depth of 89 feet; however, within the required search area the minimum clearance depth obtained is 90 feet. As the clearance depth ranges from 6 to 10 feet shoaler than the hydrography within the assigned circle of search, this wreck is not considered disproved. 1901 WK PD recommended that this item be charted in its reported position as a nondangerous sunken wreck, position doubtful, with a label in parentheses: (cleared 90 feet).

Subsequent hydrographic survey H-9885 (1980) located a submerged well in Latitude 28°35'57"N, Longitude 95°04'06"W and a watch or station buoy within the the area cleared by this investigation. The current edition (1984) of chart 11321 shows two platforms labeled "TOC-GA-391-A&B" and no buoy in this position. The current editions of the other charts common to this area do not have any platforms, submerged wells, or buoys charted in this position. It is recommended that the chart compiler research the status of these charted platforms and reflect the most current available information on all affected charts.

- 2) Presurvey Review Item #3 (AWOIS #00245), a charted dangerous sunken wreck, position approximate in Latitude 28°30'N, Longitude 94°54'W, originated with Local Notice to Mariners No. 126 of 1966 and is identified as the wreck of the SADIE S, a fishing vessel built in 1953, U. S. Coast Guard Registry No. 0265287, 63 gross tons, 58.7 feet in length, a beam of 18.5 feet, a moulded depth of 8.2 feet, and was sunk in November of 1966. This wreck is presently charted (the 1985 editions of the charts) as a nondangerous sunken wreck, position doubtful in the previously reported position from advance information from the present survey (FE-285WD). This wreck was not found by the present survey. The present survey cleared a search area exceeding the one nautical mile radius circle of search around the reported position by a minimum effective depth of 108 feet. As the clearance depth ranges from 4 to 11 feet shoaler than hydrography within the common area, this wreck is not considered disproved. Given the vessel's size and the clearance depths off the bottom, it is doubtful that the vessel is in the area surveyed. It is recommended that this item be charted as a nondangerous sunken wreck, position doubtful, with a label in parentheses: (cleared 108 feet).
- 3) Presurvey review Item #5 (AWOIS #00236), a charted dangerous sunken wreck, position approximate in Latitude 28°24'N, Longitude 94°54'W originated with Local Notice to Mariners No. 87 of 1966 and is identified as the wreck of the SINTPAT, a 55-foot long trawler which burned and sank in July of 1966. The wreck was reported as being sunk in 80 feet of water and the depths in the area of the reported position are 122 to 129 feet which indicates the strong possibility of an erroneous reported position. wreck is presently charted (the 1985 editions of the charts) as a nondangerous wreck, position doubtful in the previously reported position from advance information from the present survey (FE-285WD). This wreck was not found by the present The present survey cleared a search area exceeding the required one nautical mile radius circle of search around the reported position by a minimum effective depth of 113 feet. As the clearance depth ranges from 9 to 16 feet wK shoaler than the hydrography within the common area, this wreck is not considered disproved. It is recommended that this item be charted as a nondangerous sunken wreck, position doubtful, with a label in parentheses: (cleared 113 feet).
- 4) Presurvey Review Item #5a (AWOIS #00227) originated with a report of a vessel sinking on September 22, 1977 by the NOAA Ships RUDE and HECK during this survey (FE-285WD). This wreck is identified as the fishing vessel (trawler) FIRST MATE (U. S. Coast Guard Registry # 0279126) and is described as a wooden vessel, 48 gross tons, 53.9 feet in length, a beam of 18.2 feet, and a moulded depth of 7.3 feet. This wreck is presently charted (the 1985

editions of the charts) as a 93-foot (15-fathom) depth on a wreck in Latitude 28°21.77'N, Longitude 94°48.45'W from advance information from the present survey (FE-285WD). The present survey located this wreck in Latitude 28°21'46.4"N (28°21.77'N), Longitude 94°48'27.1"W (94°48.45'W) in depths of 134 feet. This wreck was hung in two directions by a least effective depth of 95 feet and cleared in two directions by a minimum effective depth of 92 feet. It is recommended that this item be charted as a nondangerous sunken wreck, cleared by 92 feet, in the position determined by the present survey.

b. Aids To Navigation

Two fixed aids to navigation were used as visual control (calibration) stations and are listed in section D. and Attachment IV.C. of the Descriptive Report. No floating aids to navigation were located by this survey and no floating aids are charted within the common area of this survey.

8. COMPLIANCE WITH INSTRUCTIONS

Compliance of this survey with the Project Instructions was not considered during this modified processing.

9. ADDITIONAL FIELD WORK

In general the adequacy of this survey was not considered during modified processing, except as it serves charting needs. No additional field work on the items completed by this survey is recommended.

10. MISCELLANEOUS

- a. No splits exist within the areas covered by this survey. Overlap of adjacent strips is adequate within all the areas cleared by wire drag on the present survey.
- b. The survey field records are incomplete as the Guide Vessel data, journals, and effective depth diagrams could not be found in the survey's volumes for part of "F" day, all of "G" and "H" days, and part of "J" day. Strips F-2, G-2, and J-1 are valid strips used in clearance of Presurvey Review Items #1 and #5. The lack of this survey information hampered the processing of this survey; however, the End Vessel volumes and records, the field strips, the lift records, and the Descriptive Report supplied sufficient information to process and plot this data under the modified processing procedures.
- c. The wire drag data smooth plotted and attached to this report for Presurvey Review Items #1, #3, and #5 was smooth plotted at the 1:40,000 scale to facilitate the

inclusion of the smooth plots in this report on $8\frac{1}{2}$ " by 11" mylar sheets. The plot of Presurvey Review Item #5a was smooth plotted at the 1:20,000 scale. This is consistent with section 2.6. of the Project Instructions.

Maurice B. Hickson, III

Cartographer

Modified and Limited Verification of Field Data

Modified and Limited Evaluation and Analysis

INSPECTION REPORT FE-285WD

The completed survey has been inspected with regard to survey coverage, investigation of hangs and clearance depths, cartographic symbolization, and verification or disproval of charted data. The survey complies with National Ocean Service requirements except as noted in the Evaluation Report. The survey records comply with NOS requirements except where noted in the Evaluation Report.

Inspected

R. D. Sanocki

Chief, Hydrographic Surveys

Processing Section


Hydrographic Surveys Branch


David B. MacFarland, Jr., CDR, NOAA Chief, Hydrographic Surveys Branch


Approved November 4, 1986


Ray E. Moses, RADM, NOAA

Director, Atlantic Marine Center










DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

National Ocean Survey



MARINE CHART BRANCH **RECORD OF APPLICATION TO CHARTS**

FE-285WD FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. .

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

EXAMINED FOR NIM

CHART	DATE	CARTOGRAPHE	R	REMARKS
11340	9130/87	1. Sterart	NW	Full Part Before After Marine Center Approval Signed Via
112 10	113518	9		Drawing No. #69
		10		
11330	3/8/88	CORDTS	ww	Full Part Before After Marine Center Approval Signed Via
				Drawing No. 4 4th Ed.
			. 444 . 4	
11300	3/8/88	CORDTS	ww	Full Part Before After Marine Center Approval Signed Via
	,	4		Drawing No. 42 27 " Ed.
	- 1 - 1	0.0.40	WW	Full Part Before After Marine Center Approval Signed Via
411	3/8/88	CORDTS		
		i		Drawing No. 16 39 Ed.
11321	3/8/88	CORDTS	ww	Full Part Before After Marine Center Approval Signed Via
1122.	3/ 3/ 3 3	<u> </u>		Drawing No. 31 23 vd Ed.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
	-			Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
				Drawing No.
				Full Part Before After Marine Center Approval Signed Via
W. 100				Drawing No.